

NATIONAL CENTRE FOR AQUATIC ANIMAL HEALTH
COCHIN UNIVERSITY OF SCIENCE AND TECHNOLOGY

Fine Arts Avenue
Cochin 682016, Kerala, India
Email: ncaah@cusat.ac.in

Ref. No.: NCAAH/PLEASE/2024-25/

06-07-2024

Quotation Notice

Competitive quotations are invited for Earth filling and Laying Paver blocks at CUCEK Mini campus, Pulincunnu. Sealed covers containing quotation superscribed " **Earth filling and Laying Paver blocks**" due on 12/7/2024 should reach the under signed on or before 12/7/2024. Reference No. of the quotations notice should be marked on the top of the envelope. Any quotations received after the time fixed on the due date will be rejected. In this context you may please note the following points.

The complete details of the bidder along with **full address, GST Registration Certificate copy, e-mail id, mobile number** for speedy communication may also be invariably enclosed.

Sl no.	Quantity	Particulars	Unit	Rate	Rate in Words	Amount
1	18.000 cum	Filling with contractor's own earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m as per direction of site Engineer-in-charge	cum	548.85	Rupees Five hundred and Fourty eight and paisa eighty five Only	9879.30
2	5.000 E	Engaging Man coolie	E	917.28	Rupees Nine hundred and seventeen and paisa twenty eight Only	4586.40
3	30.000 sqm	Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M - 30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge	sqm	1055.88	Rupees One thousand Fifty five and paisa eighty eight Only	31676.40

4	0.315	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 nominal size)		7113.44	Rupees Seven thousand one hundred and thirteen and paisa forty four	2240.73
5	1.261cum	Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15 cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15cm in: CM 1:6 (1 cement :6 coarse sand) etc complete	cum	6373.30	Rupees Six Thousand Three Hundred and seventybthree and paisa Thirty Only	8036.73
				Total		56419.56
				Say		56420.00

I/We agree to undertake to execute the above work% (.....
..... percentage) above/below /Estimate
Rate . Excluding GST.

Contractor



[Handwritten Signature]

DIRECTOR
National Centre for Aquatic
Animal Health

Director
National Centre for Aquatic Animal Health
Cochin University of Science & Technology